भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

SANTOSH KUMAR

OFFICE NO. - 207, FAIZAL IMAM COMPLEX , FRAZER ROAD , PATNA

Date: 14-03-2018

System Generated Auto Assessment for Height Clearance

1. Airports Authority of India (AAI) in pursuance of responsibility conferred by and as per the provisions of Govt. of India (Ministry of Civil Aviation) order GSR 751 (E) dated 30th Sep. 2015 for Safe and Regular Aircraft Operations has assessed the site data filled by the applicant.

2. Assessment details for Height Clearance:

NOCID :	**PATN/EAST/B/031418/286987**
Applicant Name :	**UmaShankar Kumar**
Type of Structure :	**Building**
Site Address :	**GEETANJALI VATIKA GREEN CITY , PLOT NO. - 46,33,35,30,06. MAUZA - ILAHIBAGH**
Site Coordinates :	**85 11 23.48-25 34 06.05, 85 11 24.12-25 34 13.16, 85 11 33.01-25 34 05.27, 85 11 34.52-25 34 10.01,**
Site Elevation AMSL in Mtrs as Submitted by Applicant:	**52 M**

Your site is located at a distance 10219 mts from ARP and lies in the grid M19 of the published CCZM of Patna airport. The Permitted top elevation for this grid is 112 mts.

Since the requested top elevation 84 mts in AMSL is below CCZM permitted top elevation, the NOC for height clearance is not required from Airports Authority of India.

3. This assessment is subject to the terms and conditions as given below:

a. The site-elevation and site coordinates provided by the applicant are taken for calculation of the permissible top elevation for the proposed structure. If,however, at any stage it is established that the actual data is different from the one, provided by the applicant, this NOC will become invalid.

b. The assessment is further subject to the provisions of Section 9-A of the Indian Aircraft Act, 1934 and any notifications issued there under from time to time including the Aircraft(Demolition of Obstruction caused by Buildings and Trees etc.) Rules,1994.

c. The applicant is responsible to obtain all other statutory clearances from the concerned authorities including the approval of building plans. This assessment for height is to ensure the safe and regular aircraft operations and shall not be used as document for any other purpose/claim whatsoever, including ownership of land etc.

d. This assessment has been issued w.r.t. the Civil Airports as notified in GSR 751(E). Applicant needs to seek separate NOC from Defence, if the site lies within jurisdiction of Defence Airport.

राजीव गांधी भवन सफदरजंग हवाई अड्डा नई दिल्ली–110003 दूरभाष : 24632950

This assessment is system auto generated and thus does not require any signature

Designated Officer

Region Name: EAST

Address: General Manager Airports Authority of India, Regional Headquarter, Eastern Region, N.S.C.B.I Airport, Kolkata-700052

Email ID: gmatmer@aai.aero

Contact No: 033-25111293

UMASHANKAR KUMAR
Architect

Regd.no : CA/2011/54023

Add: Hartali more,Boring cainal Road,Patna
web: www.aryanarchitects.com
Mo: 09693615566 , 09334999262

Ref. no. 28/Fire/Ltr.

Date : 21/09/2018

To,

The State Fire Officer
Budh Marg , Lodipur, Patna, Bihar

Subject: Regarding Suggestion of Fire Precautionary Measures for the Proposed Residential Building

Dear Sir,

I would like to draw your kind attention for the subject as stated above. I require your suggestion of fire precautionary measures of the PROPOSED BUILDING FOR to be (...G.H.....) constructed on .....Santush.....Kumar.....
S/o ....Sri..Pulam....Kumar.....Thana no. -.....11.9.....
Khata no. 02 05 08 04 18 S.Plot No. 06.3546..33..30.31
Thana. -By-pass.., Mauza -Ilati Bigha, Dist. - Patna

Is Situated Over, ...12:20..... Mts. Wide Road.

Thanking you,

Yours sincerely,

Asom Kumar
7091136870

AR. Umashankar Kumar
Registered Architect
Reg. No.-CA/2011/54023

(Ar. Umashankar Kumar)

Received
21/09/18

Provisional Fire Clearance **(Above 15Mtr. Height)**

Letter No. 1065 /
OFFICE OF THE STATE FIRE OFFICER , BIHAR , PATNA.

From,

Clement Florian,
State Fire Officer,
Bihar, Patna.

To,

Sri Umashankar Kumar ,
Architect,
Regd. No.- CA/2011/54023,

Patna Dt. 19/02/2015.

Ref :- This office letter no. 2837 dt. 16/09/13 & Your letter no. nil dt. 18/09/13.

Sub :- The views regarding proposed fully residential building of above 15 mtr. in height to be constructed at Mauza - Sampatchak, Distt.- Patna.

Sir,

With above mentioned subject the present plan was again received to this office on 12/01/15 after rectification. The first plan was received to this office on 30/05/14 vide letter no. 102/14/ILH1/G.V.P.L. dt. 29/05/14 which was returned for rectification vide this office no. 4416 dt. 24/12/2014. The corrected plan was again examined by the committee.

During examination of the plan it was found that a G+9 (Total B/U area-6488.72 Sqm.), fully residential building, shall be constructed on 40 feet wide road belongs to Baijnath Prasad, S/O- Late Ram Autar Singh, on having S. Plot no.-33, Khata no.-04, Thana no.-119 at Mauza – Sampatchak, Distt.- Patna.

We clear the plan after giving following advice/suggestions/ recommendations based on NBC guideline, local building by laws & the local circumstances which must be followed by the concerned Architect / Developer/ Land owner as the case may be.

i) **Construction :**

a) The whole construction of the proposed building shall be carried out as per approved plan drawing conforming the relevant building rules of local Municipal Corporation.
b) The floor area exceeds 750 m ^{2} shall be suitably compartmented by separation walls up to ceiling level having at least two hours Fire resisting capacity.
c) The interior finish decoration of the building shall be made low flame spread materials conforming I.S. specifications.
d) Provision of ventilation at the crown of the central core-duct of the building shall be provided.
e) Arrangements shall have to be made for sealing all the vertical ducts by the materials of adequate Fire resisting capacity.

ii) **Open Space & Approach :**

a) The open space surrounding the building shall conform the relevant building rules as well as permit the accessibility and maneuverability of Fire appliance with turning facility.
b) The approach roads shall be sufficiently strong to withstand the load of Fire Engine weighting up to 20 M.T.
c) The width and height of the access gates into the premises shall not be less than 4.5 M and 5M respecting abutting the road.

iii) **Stair Case :-**

a) The Staircase of the building shall be enclosed type. Entire construction shall be made of brick / R.C.C. type having Fire resisting capacity not less than 4 hours respectively marked in the plan.
b) The Staircase of the building shall have permanent vents at the top equal to 5% of the cross sectional area of the staircase enclosures and openable sashes at each floor level equal to 15% of the said cross section are shall have to be provided in the external wall of the building.
c) All the Staircase of the building shall be negotiable to each other in each floor without entering into any room and shall be extended up to respective terrace. The roof of the Stair wall shall be 1M above the surrounding roof area.
d) The width of the Staircases and corridor and travel distance of different categories of occupancies shall have to confirm the relevant building rules.
e) In case of two staircase, one must be on outer wall.

iv) **LIFT :-**

a) The walls of the Lift enclosure of the building shall be at least two hours Fire resisting type respectively marked in the plan with the event at top of area not less than 0.2m².

b) The lift of the building shall be designed at high speed "Fire Lift" and conspicuously indicated marked in the plan.

c) In case of failure of normal electric supply, it shall automatically trip over to alternate supply. For apartment houses these change over of supply could be done through manually operated change over switch. Alternatively, the lift shall be so wired that in case of power failure, it comes down at the ground level land comes to stand still with door open.

d) Arrangement shall be provided for extraction of smoke in all the lift shaft by incorporation smoke venting system designed to permit 30 Air changes per hour in case of Fire and shall be of such design as to operate on actuation of sprinkler or Fire Alarm. In case of failure of normal electric supply. It shall automatically trip to alternate supply.

e) All other requirements shall conform the I.S. specification including the communication facility in the lift cars connecting with the Fire Control Room of the building.

v) That active Fire protection system such as wet cum down comer system with landing valve and hose reel at each floor incorporated with 900 LPM pump at Terrace level, ISI marked Fire extinguishers as per I.S 2190/1992, F.R. check door, manual call alarm point, Fire safety luminescent sign & other Fire precautionary measures as mentioned in NBC be provided before occupancy.

vi) That an underground water static tank of not less than 50,000 Ltrs. capacity with automatic refilling arrangements prefebly on front side where Fire Brigade vehicles can reach easily & overhead water static tank of not less than 10,000 Ltrs. capacity should be made available before occupancy.

vii) That the internal finishing shall be non-combustible or class – I surface spread of flame.

viii) That electric cables must be shield at each floor with intumescent coating .

ix) That Fire exit drill be carried out regularly at least twice in a year after occupation.

x) That the building must be constructed on at least 40 feet wide road and it is responsibility of the concerned Architect to be ensure the road width because he is the passing authority.

xi) That AMC should be given to a qualified firm or person for the maintenance of above recommended Fire equipments.

xii) That the setback shall be checked by the Architect / Passing authority as per the established rule. If any thing wrong , the Architect / Passing authority shall be held responsible.

xiii) It is hereby made clear that in case of any legal dispute arising in future, in which above recommendations have not been complied, the responsibility will fall entirely upon the Developers/ Architect/ Landowner as the case may be and not on the recommending Govt. authority (i.e. the office of the State Fire Office, Bihar).

This shall be treated as provisional. On compliance of all the above Fire and Life Safety recommendations, this office shall be approached for necessary inspection and testing of the installation, Final in favor of the occupancy shall be issued on being satisfied with the tests and performances of safety aspects of installation of the building.

N.B. - Any deviation and changes the nature of use of the building in respect of the approved plan drawing without obtaining prior permission from this office, this provisional will be treated as cancelled.

The maps are being returned with sign and stamp .

Yours faithfully,

18/2/15

(Clement Florian)

Encl – As Above