2

SCHEDULE OF DOORS & WINDOWS

SL.NO.	TYPE	WIDTH	SILL.	HEIGHT
1.	D	1.07	0.00	2.13
2.	D1	0.99	0.00	2.13
3.	D2	0.91	0.00	2.13
4.	D3	0.76	0.00	2.13
5.	W	1.52	0.76	1.83
6.	W1	1.22	0.76	1.83
7.	W2	0.92	1.07	1.52
8.	W3	0.61	1.83	0.61

AREA STATEMENT

TOTAL PLOT AREA AS/SITE = 1714.05 SQM.
TOTAL GROUND FLOOR B/U AREA = 34.27 SQM
TOTAL 1ST FLOOR B/U AREA = 825.66 SQM
TOTAL 2ND FLOOR B/U AREA = 839.11 SQM
TOTAL 3RD FLOOR B/U AREA = 839.11 SQM
TOTAL 4TH FLOOR B/U AREA = 839.11 SQM
TOTAL ALL FLOOR B/U AREA = 4216.37 SQM
F.A.R. ACHIEVED = 2.46

PARKING CALCULATION

TOTAL B/U AREA = 4216.37 SQM.
REQUIRED PARKING @25%
OF TOTAL B/U AREA = 1054.09 SQM.
TOTAL COVERED PARKING AREA=791.39 SQM.
OPEN PARKING AREA = 300 SQM.
TOTAL PROVIDEDPARKING AREA= 1091.39 SQM.

WATER TANK CALCULATION

TOTAL NO. OF FLAT = 40 NOS
ONE FLAT 5 PERSON
TOTAL NO OF PERSON = 40 X 5 = 200
ONE PERSON REQU. WATER = 135 LTR./DAY
TOTAL REQU. WATER = 200 X 135 = 27000 LTR./DAY.
TOTAL REQU. AREA OF WATER TANK=27.00 CUM
TOTAL WATER REQ. FOR FIRE FIGHTING=20,000 LTRS.
TOTAL REQ WATER = 27000 + 10000 = 37000 LTRS.37 CUM.
TOTAL PROVIDED WATER TANK
(1) 3.50 X 2.13 X 1.52 = 11.33 CUM.
(2) 3.50 X 3.13 X 1.52 = 16.63 CUM.
TOTAL PROVIDED WATER = 35.09 CUM.

PLOT DETAILS.

M/S SRI MATESHWARI CONSTRUCTIONS
THROUGH ITS PATNER
SRI LAXMI PRASAD
SO/LATE GHURA PRASAD
AT MAUZA JAMSAUT
PLOT NO. -2107
KHATA NO. -496
THANA NO. -30
TAUZI NO. -3084
THANA- DANAPUR
DIST.- PATNA

NORTH | SCALE 1:100/1:200 | DRG.NO. 01/02

SHAILENDRA KUMAR
Structural Engineer
Empanelment No STRE/10/15
Nagar Parishad, Danapur, Nizamat

SIGN. OF OWNER | SIGN. OF ARCHITECT

Building Plan No...8/16-17...
निम्नांकित शर्तों के साथ भवन मानचित्र की स्वीकृति दी जाती है।
सरकारी या किसी दूसरे के जमीन का अतिक्रमण न रखना होगा, तथा पथ एवं सड़क के लिए कि संबंधित 2014 के अनुसार अपनी जमीन होगा। भवन भू-कम्पकारी बनाना होगा तथा भवन से सम्बन्धी नाला तक जल निकासी है। खर्च से मार्ग निर्माण करना होगा।
बरसाती पानी नाली के लिए सुरक्षित रखने की नि भवन मानचित्र स्वतः रद्द समझा जायेगा एवं खड़े किये गये भवनांश अवैध माना जायेगा। मानचित्र की स्वीकृति केवल तीन वर्ष के लिए होगी। भवन में रहने के पूर्व NOC प्राप्त करना तकनीकी सहायक / अभियंता की अनुशंसा के ...
पर पारित।

Nagar Parishad Danapur Nizamat
नगर कार्यपालक पदाधिकारी
नगर परिषद, दानापुर निजामत

KYE PLAN
SCALE1'=330'

LOCATION PLAN
NOT TO SCALE

SITE PLAN
SCALE1:200

TYP.PLAN OF SEPTIC TANK.

TYP. SECTION ON Z-Z

RECHARGE BORE WELL SECTION A-A

TYP. PLAN OF RECHARGE BORE WELL

UNDER GROUND FIRE FIGHTING WATER TANK 20,000 LTR.

OVERFLOW CONNECTED TO RECHARGE WELL

PROPOSED RESIDENTIAL BUILDING(G+5)

OPEN PARKING

S.T

SOIL LINE

20,000 LTRS. U.G.W.T.

9.15 WIDE ROAD

BALAJI NAGAR ROAD

KHAGUL ROAD

APPLICANT PLOT

G.D.GOENKA SCHOOL

TERRACE FLOOR PLAN

MACHINE ROOM 3.05X2.08

(01)WATER TANK 5.56X2.13X1.52

(02)WATER TANK 5.56X2.44X1.52

2ND.& 3RD.& 4TH FLOOR PLAN

1ST.FLOOR PLAN

GROUND & PARKING FLOOR PLAN

TWO WHEELER PARKING

3.78 DRIVE WAY

GUARD ROOM 2.13X2.44

TOIL. 1.12X 2.44

LIFT 1.52X 1.83

LOBBY 5.04X2.13

LOBBY 5.04X2.44

1.75 m wide CORRIDOR