

SPECIFICATION:-

1. FOUNDATION - R.C.C. UNDER REAMED PILE FOUNDATION 6.0 M DEEP WITH R.C.C. AS/ STRUCTURAL ENGINEER.
2. SUPER STRUCTURE - 1st CLASS BRICK WORK IN SUPER STRUCTURE WITH CEMENT MORTER 1:6.
3. PLINTH - HEIGHT P.L. AND G.L. AS SHOWN IN SECTION.
4. FLOORING - 0.025M TH. L.P.S. FLOORING OVER 0.125M TH. DRY RAMMED KHOA OVER 0.075 M TH. BRICK FLAT SOLING OVER SAND FILLING.
5. ROOF - 0.10M TH. AVERAGE LIME TERRACING OVER R.C.C. ROOF SLAB.
6. DOORS - CHOWKHATS OF DOORS TO BE SAL WOOD.
7. WINDOWS - ALL WINDOWS TO BE FULLY GLAZED IN STEEL.
8. PLASTER - 0.12M TH. CEMENT PLASTER ON BOTH SIDE OF BRICK WORK.
9. COLOURING - COLOUR OR WHITE WASH AS/CHOICE

SIGNATURE OF OWNER.

ARCHITECT/ENGINEER.

PATNA MUNICIPAL CORPORATION

PATNA REGIONAL DEVELOPMENT AUTHORITY (DISSOLVED)

P/Chit 30/11/18
Case No. P.R.V. - 5141.3/88.20.....18.....

Revitalization of Plan Accorded Under Section 314,

314, 316 & 317 of the Bihar Municipal Act. 2007

by Municipal Commissioner, Patna on.....

Date 31/10/18.....

DECLARATION OF PLAN ACCORDED

RAH
30-11-18

Eulham
30/11/18
मुलाम रब्बानी
उप निदेशक
पटना नगर निगम