कार्यालय, मुजफ्फरपुर क्षेत्रीय विकास प्राधिकार (विघटित), मुजफ्फरपुर नगर निगम, मुजफ्फरपुर

पत्रांक.....359..... दिनांक...19-08-2017.

प्रेषक,

नगर आयुक्त

मुजफ्फरपुर क्षेत्रीय विकास प्राधिकार (विघटित)

मुजफ्फरपुर नगर निगम, मुजफ्फरपुर।

सेवा में

श्री/~~श्रीमती~~ ...धीरेन्द्र कुमार & श्री शैलेन्द्र कुमार...

पिता/~~पति~~...श्री गजेन्द्र नारायण...

ग्राम/मोहल्ला...रसुलपुर जिलानी, दामुचक, मुजफ...

थाना .....350.....मुजफ्फरपुर।

विषय :- प्लान केस सं0-...27-.../17.../2017.... भवन निर्माण का नक्शा की स्वीकृति।

महाशय,

आपका भवन निर्माण का नक्शा मोहल्ला ...रसुलपुर जिलानी, दामुचक...

वार्ड सं0.....27..... सर्वे प्लॉट नं0...145क (अंश) (गाध (अंश.....मुजफ्फरपुर की स्वीकृति बिहार नगरपालिका अधिनियम-2007 की धारा-419 के द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए अधिनियम की धारा-314, 315, 316 एवं 317 के अन्तर्गत दी जाती है। स्वीकृत नक्शा की .....दो.....प्रतियाँ संलग्न है।

यह आदेश स्वीकृति की तिथि से अगले तीन वर्षो तक वैध है। इस बीच आपको मकान का निर्माण पूरा कर आर्किटेक्ट/अभियंता के माध्यम से निर्माण कार्य पूरा होने का प्रमाण-पत्र देना है। ऐसा नहीं करने पर दण्ड के भागी होंगे।

नगर आयुक्त

मुजफ्फरपुर क्षेत्रीय विकास प्राधिकार (विघटित),

मुजफ्फरपुर नगर निगम, मुजफ्फरपुर।

21.8.17

PLAN OF THE PROPOSED RESIDENTIAL EARTH QUAKE RESISTANT BUILDING TO BE BUILT

BY - (1)SRI DHIRENDRA KUMAR
(2)SRI SHAILENDRA KUMAR
BOTH S/O SRI GAJENDRA KARAIAL
AT - KUTHPUR ZUAMDAMUCHAK
CIRCLE - MUSHARI WARD NO -
P.S. - KEZIMOHAMMADPUR P.S.NO - 430
KHATA NO - 458, 69
S.P.NO - 145/KA PART KHAGA PART 144
DISTT - MUZAFFARPUR

AREA STATEMENT

TOTAL PLOT AREA	=	6222.00 SFT	
TOTAL BASEMENT B/U AREA	=	176.00 SFT(R&D)	
BASEMENT FLOOR PARK AREA	=	[illegible]	
GROUND FLOOR B/U AREA	=	3844.36 SFT(R&D)	
1st FLOOR B/U AREA	=	3844.36 SFT(R&D)	
2nd FLOOR B/U AREA	=	3844.36 SFT(R&D)	
3rd FLOOR B/U AREA	=	3844.36 SFT(R&D)	
TOTAL B/U AREA=15377.44+4947.36=		19823.80 SFT	
% OF COVERED AREA = 46.75 %			
% OF OPEN AREA = 53.25 % (I.R. 1.67)			

SCHEDULE OF DOOR & WINDOW

TYPE	SIZE	REMARKS
D	3'-6" x 7'-0"	FULLY PANELLED
D1	3'-0" x 7'-0"	FULLY PANELLED
D2	2'-6" x 7'-0"	FULLY PANELLED
W	6'-0" x 4'-0"	FULLY GLAZED
W1	3'-0" x 4'-0"	FULLY GLAZED
W2	3'-0" WIDE x 3'-0"	FULLY GLAZED
V	2'-0" x 3'-0"	FULLY GLAZED

GENERAL SPECIFICATION :-

COLUMN SCHEDULE

NO.	PROFILE SIZE	DEPTH	WIDTH	REINFORCEMENT
C1	9" x 12"	12"	9"	4 NOS 12 MM ø
C2	9" x 15"	15"	9"	4 NOS 12 MM ø
C3	9" x 18"	18"	9"	4 NOS 12 MM ø
C4	9" x 21"	21"	9"	4 NOS 12 MM ø
C5	9" x 24"	24"	9"	4 NOS 12 MM ø

APPLICANTS SIGN :-
① Dhirendra Kumar
② Shailendra Kumar

STRUCTURE ENGINEER :-
By
Er. AJIT KUMAR

APPROVED BY :-

FRONT ELEVATION

RIGHT SIDE ELEVATION

SITE PLAN
SCALE 1"=10'

SECTION AT-A'

SECTION AT-B-B

TERRACE FLOOR PLAN

BASEMENT FLOOR PLAN

GROUND FLOOR PLAN

1st, 2nd & 3rd. FLOOR PLAN

DETAIL PLAN OF SEPTIC TANK

TYPICAL TWO WAY R.C.C. SLAB

TYPICAL COLLUM FOOTING

TYPICAL R.C.C. WALL DETAIL

TYPICAL COLLUM FOOTING

TYPICAL SECTION OF LINTEL

TYPICAL DETAIL OF RAFT SLAB