

LOCATION PLAN
NOT TO SCALE



KEY PLAN

PARKING CALCULATION.
TOTAL B/U AREA = 8862.28 Sqm.
PARKING AREA REQUIRED (AS/TABLE NO-19, S.No-3)
@ 25% = 8862.28 X 25% = 2215.57 Sqm.
PARKING AREA PROVIDED AT COMBINED BASEMENT
= 3659.39- (Basement Flr B/U Area+Ramp Area)
= 3659.39 - [39.87+{(3.73X12.19) +(4.98X17.45)]
= 3659.39 - (39.87+ 45.47 + 85.16) = 3438.79Sqm.
PARKING AREA PROVIDED AT COVERED Gr.FLR (BLOCK-A)
= 790.98 - (B/U AREA+Ramp Area)]
= 790.98 - [86.34+(4.98X17.45)]
= 790.98 - (86.34+85.16) = 619.48 Sqm.
PARKING AREA PROVIDED AT COVERED Gr.FLR (BLOCK-B)
= 694.33 - (B/U AREA+Ramp Area)]
= 694.33 - (93.49+45.47) = 555.37 Sqm.
SO, TOTAL PARKING AREA PROVIDED
= 3438.79 + 619.48 + 555.37 = 4613.60 Sqm.



BASEMENT FLOOR PLAN
SCALE -1:150



SITE PLAN
SCALE -1:200

AREA CALCULATION (BLOCK-A)	
TOTAL PLOT AREA (AS/POSESSION)	3717.00 M²
AREALEFT FOR ROAD WIDENING+EXCESS LAND	154.90 M²
NET PLOT AREA	3562.10 M²
COMBINED BASEMENT FL. B/U AREA (BLOCK-A)	39.87 M²
GROUND FL. B/U AREA	86.34 M²
FIRST FLOOR B/U AREA	768.55 M²
SECOND FLOOR B/U AREA	768.55 M²
THIRD FLOOR B/U AREA	768.55 M²
FOURTH FLOOR B/U AREA	768.55 M²
FIFTH FLOOR B/U AREA	768.55 M²
SIXTH FLOOR B/U AREA	768.55 M²
TOTAL B/U AREA (BLOCK-A)	4697.64 M²
(BLOCK-B)	
GROUND FL. B/U AREA	93.49 M²
FIRST FLOOR B/U AREA	671.62 M²
SECOND FLOOR B/U AREA	671.88 M²
THIRD FLOOR B/U AREA	671.88 M²
FOURTH FLOOR B/U AREA	671.88 M²
FIFTH FLOOR B/U AREA	671.88 M²
SIXTH FLOOR B/U AREA	671.88 M²
TOTAL B/U AREA (BLOCK-B)	4124.77 M²
TOTAL B/U AREA (BLOCK-A & B)	
=39.87+4697.64+4124.77= 8862.28 M²	
F.A.R. = 8862.28 / 3562.10 = 2.488	

PROJECT:-
PROPOSED RESIDENTIAL BUILDING FOR
1).SRI.MITHILESH KR. SINHA
2).SRI.SATISH KR. ALIAS PINTU
3).SRI.NILESH KR. ALIAS MANTU
R/o- SOUTH MANDIRI, P.O- G.P.O, P.S.- BUDHA COLONY, PATNA, AT- HAVING SURVEY PLOT NO- 331,334&335, THANA NO-07, KHATA No- 65, THANA - KANKARBAGH, MAUZA - NAVRATANPUR, BESIDES DAWARKA COLLAGE, PATNA.
DEVELOPER - SRI SHYAM INFRACON.

ALL WARDS OF LATE LAXMI NARAYAN YADAV

SHREE SHYAM INFRACON
PARTNER
Mithilesh Kr. Sinha
Satish Kumar.
SHREE SHYAM INFRACON
Vimala Chincholi
PARTNER

SIGNATURE OF OWNER

DESIGNED BY SINGH
SIGNATURE OF ARCH./ENG.
ER. SURESH PRASAD
SIGNATURE OF STR. ENG.

PATNA MUNICIPAL CORPORATION
PATNA REGIONAL DEVELOPMENT AUTHORITY (ASSOLVED)
P/Navratanpur/RES/07/0138/2016
Sanction of Plan Accorded under Section 314, 315, 316 & 317 of the Bihar Municipal Act 2007 by the Municipal Commissioner, Patna on 28/07/2017
SANCTION OF PLAN ACCORDED

बिहार भू-सम्पदा (नियमनण और विकास) नियमावली 2017 की धारा के अधीन राज्य में गठित भू-सम्पदा [illegible] इस योजना का निरीक्षण [illegible]

सत्येन्द्र कु० सिंह
उप-निदेशक
शहरी योजना
पटना नगर निगम

सहायक निदेशक
शहरी योजना शाखा
पटना नगर निगम

NORTH

01/06