

SPECIFICATION

- (1) FOUNDATION :- R.C.C. PILE FOUNDATION.
- (2) SUPER STRUCTURE :- 1st CLASS BRICK WORK IN CEMENT MORTAR 1:6.
- (3) FLOORING :- 025 TH. P.S. FLOORING OVER 15 DRY RAMMED KHOA OVER ONE LAYER BRICK FLAT SOLING OVER LOCAL SAND FILLING.
- (4) R.C.C. WORK :- SLAB, LINTEL, STAIR, BEAM & CHAJJA IN 1:1:2 : 3 WITH PROPER REIN FOR CEMENT.
- (5) TERRACING :- 10TH AVERAGE LIME TERRACING OVER 10 TH R.C.C. ROOF SLAB.
- (6) PLASTER :- 012 TH CEMENT PLASTER ON BOTH SIDE WALL & 006 CEMENT PLASTER ON CEILING.
- (7) DRAIN :- 18 CM WIDE & 30 CM DEEP PUCCA DRAIN ROUND IN THE BUILDING.
- (8) COLOUR :- AS PER CHOICE.

:- FIRE LEGEND :-

1. UNDER GROUND WATER TANK OF 50000 LTRS. CAP. 50,000 LTRS.
2. O.H. WATER TANK OF 25000 LTRS. CAP. 25,000 LTRS.
3. FIRE RESISTANCE DOOR FD
4. FIRE HYDRANT SYSTEM H
5. HOSE REEL R
6. MANUAL CALL ALARM POINT M
7. FIRE EXTINGUISHER CO2 TYPE E
8. ILLUMINATED EXIT DIRECTIONAL SIGN EXIT
9. SEAMSE CONNECTION S
10. EMERGENCY LIGHTING SYSTEM L
11. FIRE SPRINKLER S
12. SMOKE DETECTOR A S A
13. HYDRANT SYSTEM H

SCHEDULE OF DOORS & WINDOWS

TYPE	WIDTH	HEIGHT	BILL LEV	UN. LEV	REMARK
D	1.07	2.85	0.00	0.00	BIHAR DOOR FULLY PANELLED DOORS
D1	0.91	2.13	0.00	2.13	DO
D2	0.76	2.13	0.00	2.13	DO
D3	2.13	2.13	0.00	2.13	DO

W I N D O W S

W	1.52	1.37	0.76	2.13	FULLY GLAZED WINDOW
W1	0.91	1.06	1.07	2.13	DO
W2	0.76	1.37	0.76	2.13	DO
W3	0.61	0.76	1.37	2.13	DO

PROJECT:-

- PROPOSED RESIDENTIAL BUILDING FOR
1. SRI VIJAY KR. RAI SO LATE HARAL RAI
2. SRI RAVI KR. RAI SRI VIJAY KR. RAI
3. SRI CHANDAN KR. RAI RAI
4. SRI BHARAT KR. RAI SO LATE HARAL RAI
5. SRI MURARI RAI SO LATE HARAL RAI

RESIDENT OF-BADALPURA,SAIDPURA KHATA NO- 80&86, PLOT NO- 393 & 246 THANA-KHAGAUL MAUZA - BADALPURA & SAIDPURA THANA NO - 52,51 TAUZI-535 DIST. - PATNA

DEVELOPER:- JAI SHRI SHYAM HOMES PVT LTD.

JAI SRI SHYAM HOMES PVT. LTD.

Director

SIGNATURE OF OWNER/DEVELOPER

SH. SHAILESH RANJAN, M.I.E. BSC. (ENG.) CIVIL

UP-HB- PATNA (BHAR)

MPB/Saidpurang Saidpurang (No. 18/19/16/167) / 16/10/2024

BUILDING PLAN No. 18/19/16/167/167/10/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

24/01/2024

03/04