





@100 C/C (L1)

@200 C/C (L2)

@100 C/C (L1)



CAP PC-PC
(TYPICAL)

PARKING CALCULATION:-

TOTAL BUILT UP AREA = 2400.41 SQ.FM.
TOTAL REQUIRED PARKING AREA 25% OF TOTAL BU AREA
REQUIRED CAR PARKING AREA (25%) = 600.10 SQMT
PROVIDED CAR PARKING AREA (25%) = 601.59 SQMT

WATER TANK CALCULATION

TOTAL NO OF FLAT = 38 NOS
EACH FLAT HAVE = 5.5 PERSONS
HENCE 5.5X38 = 209 PERSONS
ONE PERSON REQ 135 LTR / DAY
HENCE=209X135 LTR =28215 LTR
WATER TANK PROVIDED AT TOP OF STAIR
SIZE OF TANK =5.00 X2.00 X1.75X2 NOS = 35.00 M3 =35000 LTR

SEPTIC TANK CALCULATION

HENCE TOTAL NOS OF PERSON =209 PERSON
LIQUID CAPACITY @ 0.07 M3 / PERSON X 209
REQ AREA OF SEPTIC TANK = 14.63 M3
PROVIDE SIZE OF SEPTIC TANK
= 5.00 M X 2.50 M X1.50 M =18.75 M3

AREA CALCULATION

TOTAL PLOT AREA	= 1561.86 sqm.
TOTAL LAND LAFT FOR R/W	= 74.58 sqm.
TOTAL NET PLOT AREA	= 1487.28 sqm.
GROUND FLOOR AREA	=148.91 sqm.
FIRST FLOOR AREA	= 750.50 sqm
SECOND FL. B/U ARE	= 750.50 sqm.
THIRD FL. B/U AREA	= 750.50 sqm

TOTAL FLOOR BUILT UP AREA = 2400.41 sqm
F.A.R --------- 1.61
CAR PARKING = 601.59 sqm

PROPOSED RESIDENTIAL BUILDING FOR
(1) SRI CHAITU SINGH S/O LATE BHAGERAN SINGH (2)SMT LAXMI DEVI (3)SRI SURENDRA KUMAR SINGH (4) SRI BINAY KUMAR SINGH (5) SRI PRAMOD KUMAR SINGH
ALL S/O SRI CHAITU SINGH ,MAUZA-MAIN PURA, THANA- PATLIPUTRA ,THANA NO-02 ,
TAUZI NO.- 5123,KHATA NO-256
PLOT NO- 1785 (P), DIST - PATNA