SPECIFICATION

(1) FOUNDATION : - R C .C .PILE FOUNDATION .

(2) SUPER STRUCTURE : - 1st CLASS BRICK WORK IN CEMENT MORTAR 1:6.

(3) FLOORING : - .025 TH I . P .S FLOORING OVER .15 DRY RAMMED KHOA OVER ONE LAYER BRICK FLAT SOILING . OVER LOCAL . SAND FILLING.

(4) R .C .C . WORK : - SLAB, LINTEL , STAIR, BEAM & CHAJJA IN 1 : 1.5 : 3 WITH PROPER REINFORCEMENT .

(5) TERRACING- .10TH AVERAGE LIME TERRACING OVER .10 TH R .C .C .ROOF SLAB

(6) PLASTER : - .012 TH CEMENT PLASTER ON BOTH SIDE WALL & .006 CEMENT PLASTER ON CEILING .

(7) DRAIN : - 18 CM WIDE & 30 CM DEEP PUCCA DRAIN ROUND IN THE BUILDING .

(8) COLOUR : - AS PER CHOICE .

SCHEDULE OF DOORS & WINDOWS

TYPE	WIDTH	HEIGHT	SILL LEV.	LIN. LEV.	REMARK
D	1.07	2.13	0.00	2.13	FULLY PANELLED DOOR
D1	0.91	2.13	0.00	2.13	DO
D2	0.76	2.13	0.00	2.13	DO
W I N D O W S					
W	1.52	1.37	0.76	2.13	FULLY GLAZED WINDOW
W1	1.37	1.37	0.76	2.13	DO
W2	1.22	1.37	0.76	2.13	DO
W3	0.91	1.37	0.91	2.13	DO
W4	0.61	1.22	0.91	2.13	DO

AREA CALCULATION.

TOTAL PLOT AREA AS/ DEED = 580.61 Sqm.

TOTAL B/U AREA OF BASAMENT FLOOR = 15.19 Sqm

TOTAL B/U AREA OF GROUND FLOOR = 382.87 Sqm

TOTAL B/U AREA OF FIRST FLOOR = 398.45 Sqm

TOTAL B/U AREA OF SECOND FLOOR = 398.45 Sqm

TOTAL B/U AREA OF THIRD FLOOR = 398.45 Sqm

TOTAL B/U AREA OF FORTH FLOOR = 398.45 Sqm

TOTAL B/U AREA = 1929.54 Sqm

PROJECT:-
PROPOSED COMM.& RESID. BUILDING FOR PYARE LAL VISHKARMA , OR SON LAKHN LAL VISHKARMA, OR SON ARUN LAL VISHKARMA OR SON , SAHADEV LAL VISHKARMA OR , DOUGHTER , AT HAVING PLOT NO -1711 , KHATA NO -380, THANA NO - 367 , VILLAGE - GONAWAN, NAWADA

SHEET NO.	SCALE.	NORTH.
A/01	1 : 100	⇨

1. गीता देवी 2. अर्जुनलाल विश्वकर्मा 3. सहदेव लाल विश्वकर्मा 4. प्रतिमा देवी	Bishwamlikar pd Jun नगर परिषद् नवादा का ज्ञा० 761 दि०29-03-16 सूचीकरण सं0-03/16-18
SIGNATURE OF OWNER	SIGNATURE OF ARCHITECTS / ENGINEER.

मालती देवी
15-11-16
मुखिया
ग्राम पंचायत गोनावाँ
नवादा